SNo	Quantity	Item Name	Unit	Approved Rates of ABBUSAMB REDDY	
				Rate in Words	Rate in Figure
275	10.00	Providing and fixing white vitreous china clay,flat back or half stall urinal basin of size 580x380x350mm in the range of two with 7.5 litres P.V.C automatic flushing cistern, C.I / M.S brackets ,standard flush pipe and C.P brass spreaders with brass unions and G.I clamps, C.I trap with outlet grating and other couplings in C.P brass, painting of fittings and brackets, cutting and making good the wall and floor wherever required , including cost of materials, labour complete as per specifications. ---- All terms and condition are as per Tender Document	Unit	8980.00	Rupees Eight Thousand Nine Hundred Eighty Only
276	12.00	Providing and fixing white vitreous china clay,flat back wash basin size 630x450mm with a pair of 15mm C.P brass pillar taps with C.I / M.S brackets ,32mm C.P brass waste of standard pattern, painting of fittings and brackets, cutting and making good the wall and floor wherever required , including cost of materials, labour complete as per specifications. ---- All terms and condition are as per Tender Document	Unit	4196.00	Rupees Four Thousand One Hundred Ninety Six Only
277	4.00	Providing and fixing 453x357mm dia rectangular shape mirror with plastic moulded frame of approved make and shade with 6mm thick hard board backing including cost of materials, labour complete as per specifications. ---- All terms and condition are as per Tender Document	Unit	1274.00	Rupees One Thousand Two Hundred Seventy Four Only
278	4.00	Providing and fixing C.P brass towel rail 740mm length, 20mm dia with C.P brackets, fixed to wooden cleats with C.P brass screws including cost of materials, labour complete as per specifications. ---- All terms and condition are as per Tender Document	Unit	845.00	Rupees Eight Hundred Forty Five Only
279	20.00	do- white ---- All terms and condition are as per Tender Document	Pair	302.00	Rupees Three Hundred Two Only
280	12.00	Providing wash basin brackets of approved 1st qyuality and make confirming to ISI specifications and fixing for low down cistern as directed. Rate includes cost of materials and conveyance to work spot. -- -- All terms and condition are as per Tender Document	Pair	246.00	Rupees Two Hundred Forty Six Only
281	12.00	Providing pedestal for wash basin of approved 1st qyuality and make confirming to ISI specifications and fixing for low down cistern as directed. Rate includes cost of materials and conveyance to work spot. -- -- All terms and condition are as per Tender Document	Each	945.00	Rupees Nine Hundred Forty Five Only
282	24.00	Providing and fixing 7.5 cms to 15.00 cms dia NP grating 100 mm dia. --- - All terms and condition are as per Tender Document	Each	172.00	Rupees One Hundred Seventy Two Only
283	4.00	Providing stoneware gully trap of approved quality and make fixing in M-15 and plastering with CM 1:3 wherever necessary. (Rate includes cost of all materials, fixtures and lead).do- 15x15cms ---- All terms and condition are as per Tender Document	Each	291.00	Rupees Two Hundred Ninety One Only
284	20.00	Providing and fixing to wall, ceiling and floor unplasticised PVC 6.00 kgs/sqcm working pressure with pipe fittings, wall clips etc., and making good the wall, ceiling and floor for sanitary pipelines including cost of all materials,labour charges, HOM of acquirements and testing complete as per specifications.For Rain water pipe.- do - 110 mm dia ---- All terms and condition are as per Tender Document	m	444.00	Rupees Four Hundred Forty Four Only
285	60.00	do- 160mm dia ---- All terms and condition are as per Tender Document	m	896.00	Rupees Eight Hundred Ninety Six Only
286	2.00	Providing and fixing in position brass bib cock of approved quality 20mm nominal bore including cost of all materials, labour and HOM of equipments with all leads complete as per specifications. ---- All terms and condition are as per Tender Document	Each	262.00	Rupees Two Hundred Sixty Two Only
287	32.00	Providing and fixing in position brass stop cock of approved quality 20mm nominal bore including cost of all materials, labour and HOM of equipments with all leads complete as per specifications. ---- All terms and condition are as per Tender Document	Each	172.00	Rupees One Hundred Seventy Two Only
288	2.00	Providing and fixing in position brass gate valve with C.I wheel of approved quality (screwed end) 20mm nominal bore including cost of all materials, labour and HOM of equipments with all leads complete as per specifications. ---- All terms and condition are as per Tender Document	Each	441.00	Rupees Four Hundred Forty One Only

Contractor

Executive Engineer,
Project Division,Yelahanka

	Quantity	Item Name	Unit	Approved Rates of ABBUSAMBASIVA REDDY	
				Rate in Words	Rate in Figures
289	1.00	25mm dia nominal bore ---- All terms and condition are as per Tender Document	Each	632.00	Rupees Six Hundred Thirty Two Only
290	3.00	32mm nominal bore ---- All terms and condition are as per Tender Document	Each	1026.00	Rupees One Thousand Twenty Six Only
291	2.00	40mm nominal bore ---- All terms and condition are as per Tender Document	Each	1371.00	Rupees One Thousand Three Hundred Seventy
292	1.00	65mm nominal bore ---- All terms and condition are as per Tender Document	Each	2764.00	Rupees Two Thousand Seven Hundred Sixty
293	12.00	Providing and fixing unplasticised PVC connection pipe with brass union 15mm nominal bore 300 mm length of PVC connection including cost of all materials, labour and HOM of equipments with all leads complete as per specifications. ---- All terms and condition are as per Tender Document	Set	284.00	Rupees Two Hundred Eighty Four Only
294	2.00	Providing and fixing in position 40mm nominal bore non return valve vertical type of approved make including cost of all materials, labour and HOM of equipments with all leads complete as per specifications. ---- All terms and condition are as per Tender Document	Nos	1549.00	Rupees One Thousand Five Hundred Forty Nine Only
295	60.00	40mm dia ---- All terms and condition are as per Tender Document	m	204.00	Rupees Two Hundred Four Only
296	5.00	63mm dia ---- All terms and condition are as per Tender Document	m	375.00	Rupees Three Hundred Seventy Five Only
297	5.00	Providing and placing on terrace, polyethylene water storage tanks with manhole lid and suitable locking arrangements, making holes of suitable diameter for inlet, outlet and over flow pipes, including cost of all materials, labour, transport charges, HOM of equipments and testing complete as per specifications. (For 1000 Litre capacity) as per IS 12701 1996. ---- All terms and condition are as per Tender Document	Each	9144.00	Rupees Nine Thousand One Hundred Forty Four Only
298	5.00	Providing and fixing Chorinated Poly Venyl Chloride (CPVC) pipes conforming to IS 15778, having thermal stability for not and cold water supply including all CPVC plain and brass threaded fittings including fixing the pipe with clamp at 1.00 mtr spacing. This includes jointing of pipes and fittings with one step CPVC solvent cement & the cost of cutting chases & making good the same including testing of joints complete. (Concealed work including cutting chases and good the walls etc.,) 15mm nominal OD pipes ---- All terms and condition are as per Tender Document	m	140.00	Rupees One Hundred Forty Only
299	45.00	20mm nominal OD pipes ---- All terms and condition are as per Tender Document	m	226.00	Rupees Two Hundred Twenty Six Only
300	40.00	25mm nominal OD pipes ---- All terms and condition are as per Tender Document	m	270.00	Rupees Two Hundred Seventy Only
301	60.00	32mm nominal OD pipes ---- All terms and condition are as per Tender Document	m	334.00	Rupees Three Hundred Thirty Four Only
302	20.00	Spplying ,Installing testing and commissioning CP. Health faucet (two in one) with flexible hose,CP Angle valve, wall flange, supporting hook with screws, fixing materials and sealant to all sides of wall flange complete. ---- All terms and condition are as per Tender Document	Nos	1400.00	Rupees One Thousand Four Hundred Only
303	2.00	supplying and Installing testing and commissioning of approved make C P GRAB BAR 600 mm long , CP wall flanges, fixing materials, complete. ---- All terms and condition are as per Tender Document	Nos	2100.00	Rupees Two Thousand One Hundred Only
304	24.00	Supplying , installing, testing and commissioning U PVC multi inlet floor trap without CP grating including fittings required to connect the outlets from wash basin , kitchen sink or any other drain pipe conforming to IS with required supports with clamps in suspended piping , supporting the trap with clamps including anchor fasteners , nuts , bolts and washers all leads and lifts complete. a) 75 mm dia outlet for floor trap ---- All terms and condition are as per Tender Document	Nos	500.00	Rupees Five Hundred Only

Contractor

Executive Engineer,
Project Division,Yelahanka

SNo	Quantity	Item Name	Unit	Approved Rates of ABBUSAMBASIVA REDDY	
				Rate in Words	Rate in Figures
305	25.00	Supplying,fabricating to the required length including support length and placing in position M S angle supports (to fix the watersupply and drainage lines) shafts with a coat of primer before erecting the clamps , fixed and aligned to level with anchor fasteners , bolts , nuts and washers , coat of primer and two coats of enamel paint after the ercetion of pipe lines with all leads and lifts complete. in vertical shafts ---- All terms and condition are as per Tender Document	Kgs	85.00	Rupees Eighty Five Only
306	10.00	at terrace level ---- All terms and condition are as per Tender Document	Kgs	85.00	Rupees Eighty Five Only
307	4.00	Supplying and placing in position heavy duty P V C currah with frame of below mentioned sizes including jointing and fixing material complete. a) 160 mm dia ---- All terms and condition are as per Tender Document	Nos	1200.00	Rupees One Thousand Two Hundred Only
308	1.00	supplying , installing in position (by tieing to reinforcement or welding to reinforcement) fabricated GI puddle flanges of required dia meter as specified below , with 6mm thick MS plates of size 150 mm x150 mm for pipe sizes up to 50 mm and MS plate protruding 100mm on all sides of the pipe for diameter of pipe 65 mm and above , with two coats of anticorrossive primer with threading / suitable flanges towards the pump connection side / valve connection side , with all leads and lifts comkplete.muncipal 32 mm dia ---- All terms and condition are as per Tender Document	Nos	400.00	Rupees Four Hundred Only
309	1.00	tanker 80 mm dia ---- All terms and condition are as per Tender Document	Nos	800.00	Rupees Eight Hundred Only
310	1.00	over flow 100 mm dia ---- All terms and condition are as per Tender Document	Nos	1100.00	Rupees One Thousand One Hundred Only
311	2.00	Heavy duty manhole cover 600 x 600 ---- All terms and condition are as per Tender Document	Nos	7000.00	Rupees Seven Thousand Only
312	1.00	Air vent 80 mm dia ---- All terms and condition are as per Tender Document	Nos	1000.00	Rupees One Thousand Only
313	16.00	pvc rungs ---- All terms and condition are as per Tender Document	Nos	300.00	Rupees Three Hundred Only
314	1.00	pvc conduit 25 mm dia ---- All terms and condition are as per Tender Document	Nos	20.00	Rupees Twenty Only
315	1.00	outlet to oht 40 mm dia ---- All terms and condition are as per Tender Document	Nos	600.00	Rupees Six Hundred Only
316	1.00	Providing and constructing water meter chamber over a bed of P C C 1:4:8,in 200 mm thick solid block in C M 1:8, both internal and external plastering in C M 1:6, medium duty precast concrete cover with all leads and lifts, including curing complete. Size of chamber 750 X 750 x 600 mm clear ---- All terms and condition are as per Tender Document	Nos	12000.00	Rupees Twelve Thousand Only
317	1.00	Providing and constructing inspection chamber (for bore well) with first quality table molded bricks of standard size in C M 1:6 over a P C C bed of 1 4 8 of 100 mm thick, internal surface plastered smooth and externally finished rough including providing P C C for channeling and providing pre cast slab of 100 mm thick with frame and cover including curing all leads and lifts fixing in position fiber coated steps etc., complete. ---- All terms and condition are as per Tender Document	Nos	12000.00	Rupees Twelve Thousand Only
318	1.00	Making necessary arrangements to obtain the permission for the connection of sewage line to the BWSSB main line and obtaining connection for water supply (deposits and other incidentals shall be borne by the client). ---- All terms and condition are as per Tender Document	LS	50000.00	Rupees Fifty Thousand Only

3/1

Contractor

Executive Engineer,
Project Division,Yelahanka

	Quantity	Item Name	Unit	Approved Rates of ABBUSAMBASIVA REDDY	
				Rate in Words	Rate in Figures
319	1.00	Supplying, installing, testing and commissioning approved make submersible pump made of C.I construction suitable for buildingapplication. Thequoted rate shall also include for providing necessary safety devices viz. dry runprotection, over load relays auto level controller with necessary cables etc., complete working on 3ph 440V,50Hz, three phase systemFor pumping treated water from UG Sump to OHT vertical type - pump, horizontal distance - 40 mtrs, Vertical distance - 15 mtrs, Duty of the Pump, 3.0 lps at 40m head (1 W+ 1st.by = 1No set) ---- All terms and condition are as per Tender Document	Set	50000.00	Rupees Fifty Thousand Only
320	1.00	Supplying, Installing testing and commissioning approved make water level controller with cabling in P V C conduit (3 core & multi strand copper wire 1.5 sq mm) and automatic water level indicator digital type, indicating the level of water in percentage ---- All terms and condition are as per Tender Document	Nos	8000.00	Rupees Eight Thousand Only
321	50.00	Length of cable ---- All terms and condition are as per Tender Document	Rmt	90.00	Rupees Ninety Only
322	50.00	Length of conduit ---- All terms and condition are as per Tender Document	Rmt	40.00	Rupees Forty Only

H.V. 3/1/18

Contractor

Executive Engineer,
Project Division, Yelahanka